Sl. No.	Particulars	Unit	No	L	B	D	Qty	Rate	Amount
1	2	3	4	5	6	7	8	9	10
9	Supply ISI marked Galzanized mild seel tube (continously welded) electric resitence welded (ERW) High frequency Induction welded (HFIW) Hot finished welded type of nominal bore given beow, screwed to both ends as pe IS 554/1986 with latest amendments, pipes threaded at both end and the other protected as per specification in random lengths of 4 to 7 mtrs. conforming to IS 1239 Part I/1990 with amendments 1-5 and with all its latest amendments if any. The pipes suplied should be with BIS Mark galvanized iron pipes ISI 239 Part-1, 1990,								
		Rmtr	1	300.00			300.00	374.00	112200.00
10	Supply ISI marked G.I. and G.M. specials confirming to IS and with all its latest amendments if any.								
a	50mm dia G.I Elbow	Nos	1	60.00			60.00	123.00	7380.00
b	50mm dia G.I Union	Nos	1	15.00			15.00	248.00	3720.00
c	50mm dia G.I Collar	Nos	1	120.00			120.00	128.00	15360.00
d	160mm borewell cap with clamp set	Nos	1	5.00			5.00	740.00	3700.00
e	50mm gun metal non return valve	Nos	1	5.00			5.00	1645.00	8225.00
11	Gate valve 50mm nominal bore gun metal PRE SR 2010-11, P.No.5, I.No.134	Nos	22				22.00	1200.00	26400.00
12	Gate valve 65mm nominal bore gun metal PRE SR 2010-11, P.No.5, I.No.135	Nos	25				25.00	1500.00	37500.00
13	Gate valve 80mm nominal bore gun metal PRE SR 2010-11, P.No.5, I.No.136	Nos	14				14.00	1800.00	25200.00
									1793168.00
	KRIDL & Laqbour cess Charges 11%								197249.00
	Miscellanious								9583.00
									2000000.00
(Rupees Twenty Lakhs Only)									

Certifacates:

1. The work spot is isnepcted by Me
2. The work is found necessary and the work is not split up
3. The work spot copmes under BBMP Village Limits
4. The rates bassed on BWSSB SR 2013-14, RDED SR 2012-13

JE/AE
Ward No 14

Asst.Executive Enginne
T.Dasarahalli Sub Division

Executive Enginne
Dasarahalli Division